BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

MODIFIED SCHEDULE-B

NAME OF WORK: Maintenance of roads and footpath in ward no 12 Shettyhalli, Shettyhalli Sub Division

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor Sri Manikanta M V	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	KSRRB300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 .(PWD SR 2018-19, Page No.143, Item No. 19.1)	cum	236.3	175.00	Rupees One Hundred Seventy Five Only
2	KSRB 4-1.7 : Providing and laying in position plain cement concrete of Mix 1:3:6 with OPC @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.69 cum and fine aggregtes @ 0.56cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM (PWD SR 2018-19 Page No.13 , Item No.4.7)	cum	31.95	4286.00	Rupees Four Thousand Two Hundred Eighty Six Only
3	KSRRB M2200-5.12. Providing and laying Design mix M25 with OPC @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.7cum and fine aggregates @ 0.47cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008 - i) Upto 5m height (PWD SR 2018-19 It No 28.7.12 P. No 222)	cum	66.68	4332.00	Rupees Four Thousand Three Hundred Thirty Two Only
4	KSRRB M2200-6 : Providing TMT teel reinforcement for RCC work including starightening, cutting, bending, hooking, placing in position, lapping and /or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design(laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specification MORTH Specification No.1600 & 2200 - TMT Bars Fe 500 [PWD SR 2018-19 P. no.18 - I. no.4.46.2]	MT	4.17	56418.00	Rupees Fifty Six Thousand Four Hundred Eighteen Only

ature of the Contractor,

Executive Engineer,
Dasarahalli Division,

Scanned by CamScanner

5	Providing and fixing precast reinforced cement concrete covering slabs 10cm thick made out of M25 with OPC cememnt @340kgs per cum, 20mm and down size graded granite metal corse aggreates @0.70 cm and fine aggregates @0.74 cum with super plasticizers machine mixed, including providing and removing centering, shuttering strutting propping etc., for edges of slab with TMT steel (Fe500) cost & reinforcement charges including finishing as required with cost of reinforcement etc., complete as per the direction of Engineer-in-charge of the work.	Sqm	166.5	1211.00	Rupees One Thousand Two Hundred Eleven Only
6	Providing and fixing pre cast solid cement concrete kerb stones made out of C.C. 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc., complete. [PWD SR 2018-19 P. no.27 - I. no.5.30)	No	636	324.00	Rupees Three Hundred Twenty Four Only
7	KSRRB 800-1. Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8 [PWD SR 2018-19 P. no.180- I. no.24.1)	Cum	83.25	64.00	Rupees Sixty Four Only
8	Providing and removing centering, shuttering, strutting, propping etc.. And removal of form work for vertical surface such as walls at any thickness including attached pillars, buttresses, plinth and string courses cost of all materials, labour complete as per specifications. (Pg 16 item no 4.31 of PWD SR 2018-19)	Sqmt	591	284.57	Rupees Two Hundred Eighty Four and Fifty Seven Paise Only
9	KSRB 2-3 : Filling available excavated earth (excluding rock) in sides of foundation upto plinth in layers not exceeding 20cms. In depth, compacting each deposited layer by ramming after watering with lead upto 50m. And lift upto 1.5m. Including cost of all labour complete as per specifications. Specificaton. No. KBS 2.9 . (Pg 06 item no 2.10 of PWD SR 2018-19)	cum	172.25	159.77	Rupees One Hundred Fifty Nine and Seventy Seven Paise Only

ature of the Contractor,

Executive Engineer,
Dasarahalli Division,

Scanned by CamScanner

10	Providing and fixing precast reinforced cement concrete covering slabs 25 cm thick made out of M25 with OPC cement @ 340kgs per cum, 20mm and down size graded granite metal coarse aggregate (@0.70 cm and fine aggregate (@ 1.0 cum with super plasticizers machine mixed, including providing and removing centering, shuttering strutting propping etc for edges of slab with TMT steel (Fe500) cost & reinforcement charges including finishing as required with cost of reinforcement etc complete as per the direction of Engineer in charge of the work	Sqm	10	293.45	Rupees Two Thousand Three Hundred Twelve and Forty Five Paise Only
11	KSRB 15-19.1 Providing and applying ready mix priming coat over concrete / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after thoroughly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications.. (BCSR 2018-19. P-124, I-15.80)	Cum	83.25	29.41	Rupees Twenty Nine and Forty One Paise Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

Exec
Dasa

Scanned by CamScanner